

Statement of Work

Asphalt pavement at Udorn Transmission Station.

I. General Information

A. Introduction

The purpose of this fixed-price contract is to obtain service for U.S. Government property at the USAGM Thailand Transmitting Station, Udorn Thani. The USAGM/ Udorn station was built in 1994 and is located in Ban Dung district, 70 Kilometers northeast of Udorn Thani city. The Contractor shall provide contracting services for Asphalt paving. The performance period of this contract is 30 days from the date of the contract award.

The Contractor must furnish all tools, equipment, materials, supervision, and direct labor personnel necessary to perform and accomplish the specified requirements listed in the Scope of Work below. Contractor employees shall be on site only for contractual duties and not other business purposes.

B. Scope of work:

1. Road and Parking spaces Asphalt paving:

The current Asphalt is cracked and deteriorating due to aging, weathering, and vegetation growth. The station has an immediate need to repair and replace the asphalt paved road and parking spaces within the station's inner compound area.

The Contractor must provide all tools, equipment, materials, supervision, and direct labor personnel to perform; demolition and removal of the existing surface area, grading and sloping, sub-base installation, and Asphalt paving installation, including binder and surface course repair of asphalt paved road and parking space for 394 square meters total area located in the inner station compound. The parking area must be painted with a parking space road line.

The station will hold a site visit on *June 2, 2022*, open for all contractors to survey the work area. POC is Mr. Anuparp Saneepan, Tel. 042-271300 Ext. 114.

II. Work Requirement.

Technical Requirements:

Asphalt Pavement:

- The Contractor must provide the necessary tools, equipment, materials, supervision, and direct labor required for demolition and removal of the existing surface area, grading and sloping, sub-base installation, and Asphalt paving installation, including binder and surface course.
- The Contractor must remove the existing Asphalt or the cracked/broken surfaces, trim the Tree's roots when applicable to prevent future damage, fill and level the ground surface before re-pave with asphaltic concrete.
- The Contractor must pave the surface of the removed area with Asphalt as required, not less than 50 millimeters (mm.) of thickness and compact to the same level as the existing pavement surface.
- The Contractor must repaint parking area space lines and disabled parking space signs matching the existing paint at the area before removal.

General Requirements:

- USAGM facility operated 24 hours, seven days a week. All work shall be conducted in the areas listed here within, with emphasis on safety and business continuity.
- Unless otherwise specified, standard working days are five days per week, between the hours of 7:30 and 15:30, Monday through Friday, except for regularly scheduled holidays. Any scheduled work required out of the regular days of operations requires advance COR approval.
- The Contractor shall designate a representative who shall be responsible for on-site supervision of the Contractor's workforce at all times.
- The Contractor supervisor will serve as project manager and shall be the point of contact with U.S. Government personnel and responsible for workers' conduct and work quality.
- The supervisor shall have sufficient English language skills to communicate with members of the U.S. Government staff.
- The Contractor shall preserve peace and protect persons and property on-site. The Contractor shall maintain discipline at the site and take all reasonable precautions to prevent any unlawful, riotous, or disorderly conduct by Contractor employees. The Government reserves the right to direct the Contractor to remove an employee from the worksite for failure to comply with the standards of conduct. In case of employee removal, the Contractor shall immediately replace such an employee within 24 hours to maintain continuity of services at no additional costs to the Government.
- The Contractor shall comply with all local labor laws, regulations, customs, and practices pertaining to labor, safety, and similar matters, to the extent that such compliance is not inconsistent with the requirements of this contract.

- In case of deviation from the approved project schedule, the site supervisor shall notify the COR of the indented work area for prior approval.
- The site supervisor must notify the COR of any unforeseen reasons such as weather condition changes or material delays that may cause work delays or change of work schedule.
- The Contractor will be allowed to store work tools and equipment on the USAGM site at the pre-designated area only. Under no circumstances the U.S government is responsible for any stored tools, equipment, or materials.
- Contractor and contract works are only allowed to use the designated parking areas as directed by the COR.
- The Contractor must provide at least 50% of the workforce utilized to perform this work from the local district of Ban Dung, in Udon Thani Province.
- The Contractor must clean and haul any debris from the working area at the end of each workday.
- The Contractor must provide a five (5) year warranty on the pavement workmanship and material performed.
- The Contractor is required to perform any warranted/necessary work of pavement surface or under surface area within 14 days of the date of reporting.

Deliverables:

The following items shall be delivered under this contract:

Description	Quantity	Delivery To	Date
Project schedule	1	COR	30 days after the award
List of Personnel	1	COR	Two weeks after the award
Insurance	1	COR	Ten days after the award
Licenses and permits	1	COR	Date of award

III. Supporting Information.

A. Security

- The Contractor must submit workers' names and I.D's at least two (2) weeks prior to accessing and performing the contract at USAGM/TTS.

B. Place of performance.

- USAGM Thailand Transmitting Station Udon thani, Bandung – Phen Road, Nong Hai Village, Bandung Sub-District, Bandung District, Udon Thani Province, Thailand, Postal code 41190. Telephone +66-42-271300.

C. Period of performance.

- The working schedule at Udon Thani station to perform the task is 08:00 to 15:00 Monday to Friday, except for Thai and American holidays.
- The Contractor must complete the removal, repair, installation, and clean work within 30 workdays after receiving Notice to Proceed.
- The Contractor must report to COR immediately for any work delays or schedule changes.

D. Special Considerations.

- The Contractor must be at least five (5) years in the road and building construction business.
- Defense Base Act (DBA) insurance may be required.
- The Contractor must have health and accident insurance for their worker.
- SAM registration is needed. The Contractor can complete registration at www.sam.gov.

End of Statement of Work.